BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED SCHEDULE - B

Name of the work:Filling of potholes in ward no. 07, Byatarayanapura.

Sl. No.	Approved Qty.	Description	Unit	Rates	
				Sri. U. Ramesh	
				In Figures	In Words
1	1315.64	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	73.88	Rupees Seventy Three and Eighty Eight Paise Only
2	986.73	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 170/ Item No. 20.18/ PWD SR 2016-17	Cum	1701.08	Rupees One Thousand Seven Hundred One and Eight Paise Only
3	403.13	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications Qty upto 125%	Sqm	310.88	Rupees Three Hundred Ten and Eighty Eight Paise Only
4	1206.88	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications Qty above 125%	Sqm	310.85	Rupees Three Hundred Ten and Eighty Five Paise Only

U. Ramesh
Signature of the Contractor

25/09
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/09